



City of Cleveland

Justin M. Bibb, Mayor

Department of Finance
Division of Purchases and Supplies
601 Lakeside Avenue, Room 128
Cleveland, Ohio 44114-1080
216/664-2620 Fax 216/664-2177
www.cleveland-oh.gov

October 15, 2026

ADDENDUM 2

BID TITLE: **File No. 101-2026 – 2026 Recycled Asphalt Demo Project**

BID DUE: **Friday, October 23, 2026, at Noon**

Attention Bidders: We have been requested to issue this addendum to advise vendors of the following:

1. Answers to Questions.
2. Delete and replace "Master Index" in its entirety with the attached revised "Master Index".
3. Delete and replace "Schedule of Items" in its entirety with the attached revised "Schedule of Items."

Please ensure that a copy of this addendum is included and returned with the bid specifications furnished to you by this office, as it will have the same force and effect as if it were part of the specifications originally issued.

Signature of Potential Bidder & Name of Company

Today's Date

Thank you,

Steven Decker

Purchases & Supplies
CC: Attachments



File 101-2026 – 2026 Recycled Asphalt Demo Project

Addendum No. 2

ANSWERS TO QUESTIONS RECEIVED FROM BIDDERS

1.	Question	Whether the revised roadway locations change the estimated quantities, bid schedule, or engineer's estimate?
	Answer	The revised bid schedule of items attached with estimate quantities are attached. Engineer estimate is \$843,442.77
2.	Question	The contract-specific insurance limits and any environmental or hauling endorsements required?
	Answer	For details on insurance requirements, please review Part B of the General Conditions, specifically Section B-18 (Public Liability, Property Damage, and Automobile Insurance) and Section B-42 (Fire and Extended Coverage Insurance). No environmental or hauling endorsements are required.
3.	Question	The City's task-order invoicing and payment terms?
	Answer	This is a public improvement contract so no Task Orders will be issued. The Contractor and City inspector will confirm quantities, then submit estimate once a month with their updated schedule.
4.	Question	The applicable CSB/MBE/FBE participation goals for this procurement?
	Answer	Due to a limited pool of qualified contractors the contract received a variance so there are no goals.
5.	Question	Whether dump-truck/material-hauling subcontractors must be named in Schedules 1–4 at bid submission?
	Answer	The project has no OEO goals so there is no need to submit Schedules 1-4 at bid unless you will be utilizing subcontractors.

Table of Contents:
2026 Recycled Asphalt Demo Project (IFB 101-26)
ADDENDUM#2

1	Cover Page	1
2	Table of Contents	1
3	Ordinance No. 236-2026	1
4	Notice to Bidders	1-2
5	Part A - Instructions to Bidders	1-4
6	Part B - General Conditions	1-10
7	C Specs - Supplemental General Conditions	1-13
8	Standard D Specs Index (Green)	i-iii
9	Standard D Specs (Green)	1-75
10	DS Specification Index	i
11	DS Specifications	1-17
12	Special Provisions-Curb Ramps (Green)	1-9
13	Standard Construction Drawings	1-41
14	Monument Box and Assemblies	1
15	BP- 7.1	1-3
16	Adjustable Castings Risers	1-11
17	Partial Depth Pavement Repair Detail	1
18	Std Dwg Conc 1 - Sheet 2 and 3 of 4 revised January 14, 2020	1-3
19	Asphalt and Rubber Speed Tables	1-5
20	Change Order Check list	1
21	Prevailing Wage Rates (Brown)	1-23
22 *	Bidders Checklist (Yellow)	1-2
23 *	Vendor info form (Yellow)	1
24 *	Bid Bond (Yellow)	1
25 *	Tax Payer ID W-9 (Yellow)	1-5
26 *	Affidavit (Yellow)	1-2
27 *	Northern Ireland Disclosure (Yellow)	1
28 *	Bid Unit Price (Yellow)	1-2
29 *	Schedule of Items (Yellow)	1-9
30 *	Agreement Form (Yellow)	1
31 *	Bond	1-2
32	OEO Participaton Information Form	1
33 *	OEO Notice to Bidders (5/05/22 - Includes OEO Schedules 1-4) (Yellow)	1-21
34 *	Project Labor Agreement	1-15
35	Road Exhibits	1-9

Items with asterisk (*) shall be completed and/or signed as part of the bid package

All pages and paragraphs of the specifications are numbered. It is the responsibility of each bidder to insure that the errors or omissions are called to the attention of the Division of Purchases and Supplies and to request a correct copy of these specifications

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION		
2026 RECYCLED ASPHALT DEMO (IFB 101-26)		
ADDENDUM #2		
SUMMARY SHEET		
REF NO.	DESCRIPTION	ESTIMATED COST
1	LEE HEIGHTS BLVD. SCHEDULE OF ITEMS SUB TOTAL (\$)	
2	EDGECLIFF AVE. SCHEDULE OF ITEMS SUB TOTAL (\$)	
3	ORCHARD PARK AVE. SCHEDULE OF ITEMS SUB TOTAL (\$)	
4	TALFORD AVE. SCHEDULE OF ITEMS SUB TOTAL (\$)	
GRAND TOTAL (\$)		

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
EDGECLIFF AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
ROADWAY					
1	ITEM 609 - CONCRETE CURB CAST IN PLACE, INCLUDING REMOVAL AND DISPOSAL OF EXISTING CURB, COMPLETE IN PLACE, TO MATCH	FOOT	40		
2	ITEM 659 - SEEDING AND MULCHING, CLASS I HIGH QUALITY, AS PER D-66, COMPLETE IN PLACE	SQ.YD	10		
3	ITEM SPECIAL - CURB RAMP CR-2 COMPLETE IN PLACE WITH TILE, INCLUDING LAYOUT AND REMOVAL AS PER PLAN	CORNER	-		
SUBTOTAL ROADWAY					
DRAINAGE					
4	ITEM 605 - 4" UNDERDRAINS AS PER D-42	FOOT	40		
5	ITEM 611 - NEW CATCH BASIN AS PER CITY OF CLEVELAND STANDARD DRAWING CB-1 AND AS PER D-34	EACH	2		
SUBTOTAL DRAINAGE					
PAVEMENT					
6	ITEM 202 - PAVEMENT REMOVED (ROADWAY) AS PER D-15	SQ. YD.	49		
7	ITEM 203 - EXCAVATION AS PER D-15, COMPLETE IN PLACE AS DIRECTED BY THE ENGINEER	CU. YD.	8		
8	ITEM 255 - FULL DEPTH PAVEMENT SAWING AS DIRECTED BY ENGINEER	FOOT	84		
9	ITEM 304 - 6" LIMESTONE AGGREGATE BASE	CU. YD.	8		
10	ITEM 407 - TACK COAT (AT 0.10 GAL/SY)	GAL.	5		
11	ITEM 441 - 1-1/4" ASPHALT CONCRETE, TYPE 1 SURFACE COURSE, (448), PG64-22	CU. YD.	2.0		
12	ITEM 441 - 1-3/4" ASPHALT CONCRETE, TYPE 2 INTERMEDIATE COURSE, (448), PG64-22	CU. YD.	2.4		
13	ITEM 644 - CROSSWALK LINE, AS DIRECTED BY ENGINEER	FOOT	225		
14	ITEM 644 - STOP LINE, AS DIRECTED BY ENGINEER	FOOT	78		
15	ITEM SPECIAL - IN PLACE HOT REUSED ASPHALT PAVING, AS PER DS-6	SQ. YD.	7,000		
SUBTOTAL PAVEMENT					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
EDGECLIFF AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
PROJECT INCIDENTALS					
16	ITEM 614 - MAINTAINING TRAFFIC	LS	1		
17	ITEM 614 - MOBILIZATION	LS	1		
18	ITEM SPECIAL - MAKING AND CURING CONCRETE TEST CYLINDERS IN THE FIELD, AS PER D-76	SETS	1		
19	ITEM SPECIAL – FORCE ACCOUNT AS PER D-13	LS	1		
20	ITEM SPECIAL – FEES (1% of TOTAL SUM OF BID ITEMS)	LS	1		
SUBTOTAL PROJECT INCIDENTALS					
UNOFFICIAL TOTAL SUM (BID ITEMS 1-20) - (*)					
ALL QUANTITIES ARE APPROXIMATE AND NOT GUARANTEED.					
* The amount of the Bid Bond or Cashier's Check required of all bidders under Section A-7 and the amount of the surety bond required of the successful bidder under Section 19, shall be based upon this dollar figure.					
** Please see Exhibits C-1 through C-3A for proposed locations					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
LEE HEIGHTS BLVD. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
ROADWAY					
1	ITEM 609 - CONCRETE CURB CAST IN PLACE, INCLUDING REMOVAL AND DISPOSAL OF EXISTING CURB, COMPLETE IN PLACE, TO MATCH	FOOT	80		
2	ITEM 659 - SEEDING AND MULCHING, CLASS I HIGH QUALITY, AS PER D-66, COMPLETE IN PLACE	SQ.YD	20		
3	ITEM SPECIAL - CURB RAMP CR-2 COMPLETE IN PLACE WITH TILE, INCLUDING LAYOUT AND REMOVAL AS PER PLAN	CORNER	-		
SUBTOTAL ROADWAY					
DRAINAGE					
4	ITEM 605 - 4" UNDERDRAINS AS PER D-42	FOOT	80		
5	ITEM 611 - NEW CATCH BASIN AS PER CITY OF CLEVELAND STANDARD DRAWING CB-1 AND AS PER D-34	EACH	4		
SUBTOTAL DRAINAGE					
PAVEMENT					
6	ITEM 202 - PAVEMENT REMOVED (ROADWAY) AS PER D-15	SQ. YD.	98		
7	ITEM 203 - EXCAVATION AS PER D-15, COMPLETE IN PLACE AS DIRECTED BY THE ENGINEER	CU. YD.	16		
8	ITEM 255 - FULL DEPTH PAVEMENT SAWING AS DIRECTED BY ENGINEER	FOOT	168		
9	ITEM 304 - 6" LIMESTONE AGGREGATE BASE	CU. YD.	16		
10	ITEM 407 - TACK COAT (AT 0.10 GAL/SY)	GAL.	10		
11	ITEM 441 - 1-1/4" ASPHALT CONCRETE, TYPE 1 SURFACE COURSE, (448), PG64-22	CU. YD.	4.1		
12	ITEM 441 - 1-3/4" ASPHALT CONCRETE, TYPE 2 INTERMEDIATE COURSE, (448), PG64-22	CU. YD.	4.8		
13	ITEM 644 - CROSSWALK LINE, AS DIRECTED BY ENGINEER	FOOT	56		
14	ITEM 644 - STOP LINE, AS DIRECTED BY ENGINEER	FOOT	12		
15	ITEM SPECIAL - IN PLACE HOT REUSED ASPHALT PAVING, AS PER DS-6	SQ. YD.	7,066		
SUBTOTAL PAVEMENT					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
LEE HEIGHTS BLVD. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
PROJECT INCIDENTALS					
16	ITEM 614 - MAINTAINING TRAFFIC	LS	1		
17	ITEM 614 - MOBILIZATION	LS	1		
18	ITEM SPECIAL - MAKING AND CURING CONCRETE TEST CYLINDERS IN THE FIELD, AS PER D-76	SETS	1		
19	ITEM SPECIAL – FORCE ACCOUNT AS PER D-13	LS	1		
20	ITEM SPECIAL – FEES (1% of TOTAL SUM OF BID ITEMS)	LS	1		
SUBTOTAL PROJECT INCIDENTALS					
UNOFFICIAL TOTAL SUM (BID ITEMS 1-20) - (*)					
ALL QUANTITIES ARE APPROXIMATE AND NOT GUARANTEED.					
* The amount of the Bid Bond or Cashier's Check required of all bidders under Section A-7 and the amount of the surety bond required of the successful bidder under Section 19, shall be based upon this dollar figure.					
** Please see Exhibits C-2 through C-2A for proposed locations					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
ORCHARD PARK AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
ROADWAY					
1	ITEM 609 - CONCRETE CURB CAST IN PLACE, INCLUDING REMOVAL AND DISPOSAL OF EXISTING CURB, COMPLETE IN PLACE, TO MATCH	FOOT	40		
2	ITEM 659 - SEEDING AND MULCHING, CLASS I HIGH QUALITY, AS PER D-66, COMPLETE IN PLACE	SQ.YD	10		
3	ITEM SPECIAL - CURB RAMP CR-2 COMPLETE IN PLACE WITH TILE, INCLUDING LAYOUT AND REMOVAL AS PER PLAN	CORNER	-		
SUBTOTAL ROADWAY					
DRAINAGE					
4	ITEM 605 - 4" UNDERDRAINS AS PER D-42	FOOT	40		
5	ITEM 611 - NEW CATCH BASIN AS PER CITY OF CLEVELAND STANDARD DRAWING CB-1 AND AS PER D-34	EACH	2		
SUBTOTAL DRAINAGE					
PAVEMENT					
6	ITEM 202 - PAVEMENT REMOVED (ROADWAY) AS PER D-15	SQ. YD.	49		
7	ITEM 203 - EXCAVATION AS PER D-15, COMPLETE IN PLACE AS DIRECTED BY THE ENGINEER	CU. YD.	8		
8	ITEM 255 - FULL DEPTH PAVEMENT SAWING AS DIRECTED BY ENGINEER	FOOT	84		
9	ITEM 304 - 6" LIMESTONE AGGREGATE BASE	CU. YD.	8		
10	ITEM 407 - TACK COAT (AT 0.10 GAL/SY)	GAL.	5		
11	ITEM 441 - 1-1/4" ASPHALT CONCRETE, TYPE 1 SURFACE COURSE, (448), PG64-22	CU. YD.	2.0		
12	ITEM 441 - 1-3/4" ASPHALT CONCRETE, TYPE 2 INTERMEDIATE COURSE, (448), PG64-22	CU. YD.	2.4		
13	ITEM 644 - CROSSWALK LINE, AS DIRECTED BY ENGINEER	FOOT	60		
14	ITEM 644 - STOP LINE, AS DIRECTED BY ENGINEER	FOOT	64		
15	ITEM SPECIAL - IN PLACE HOT REUSED ASPHALT PAVING, AS PER DS-6	SQ. YD.	6,031		
SUBTOTAL PAVEMENT					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
ORCHARD PARK AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
PROJECT INCIDENTALS					
16	ITEM 614 - MAINTAINING TRAFFIC	LS	1		
17	ITEM 614 - MOBILIZATION	LS	1		
18	ITEM SPECIAL - MAKING AND CURING CONCRETE TEST CYLINDERS IN THE FIELD, AS PER D-76	SETS	1		
19	ITEM SPECIAL - FORCE ACCOUNT AS PER D-13	LS	1		
20	ITEM SPECIAL - FEES (1% of TOTAL SUM OF BID ITEMS)	LS	1		
SUBTOTAL PROJECT INCIDENTALS					
UNOFFICIAL TOTAL SUM (BID ITEMS 1-20) - (*)					
ALL QUANTITIES ARE APPROXIMATE AND NOT GUARANTEED.					
* The amount of the Bid Bond or Cashier's Check required of all bidders under Section A-7 and the amount of the surety bond required of the successful bidder under Section 19, shall be based upon this dollar figure.					
** Please see Exhibits C-1 through C-3A for proposed locations					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
TALFORD AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
ROADWAY					
1	ITEM 609 - CONCRETE CURB CAST IN PLACE, INCLUDING REMOVAL AND DISPOSAL OF EXISTING CURB, COMPLETE IN PLACE, TO MATCH	FOOT	80		
2	ITEM 659 - SEEDING AND MULCHING, CLASS I HIGH QUALITY, AS PER D-66, COMPLETE IN PLACE	SQ.YD	20		
3	ITEM SPECIAL - CURB RAMP CR-2 COMPLETE IN PLACE WITH TILE, INCLUDING LAYOUT AND REMOVAL AS PER PLAN	CORNER	-		
SUBTOTAL ROADWAY					
DRAINAGE					
4	ITEM 605 - 4" UNDERDRAINS AS PER D-42	FOOT	80		
5	ITEM 611 - NEW CATCH BASIN AS PER CITY OF CLEVELAND STANDARD DRAWING CB-1 AND AS PER D-34	EACH	4		
SUBTOTAL DRAINAGE					
PAVEMENT					
6	ITEM 202 - PAVEMENT REMOVED (ROADWAY) AS PER D-15	SQ. YD.	98		
7	ITEM 203 - EXCAVATION AS PER D-15, COMPLETE IN PLACE AS DIRECTED BY THE ENGINEER	CU. YD.	16		
8	ITEM 255 - FULL DEPTH PAVEMENT SAWING AS DIRECTED BY ENGINEER	FOOT	168		
9	ITEM 304 - 6" LIMESTONE AGGREGATE BASE	CU. YD.	16		
10	ITEM 407 - TACK COAT (AT 0.10 GAL/SY)	GAL.	10		
11	ITEM 441 - 1-1/4" ASPHALT CONCRETE, TYPE 1 SURFACE COURSE, (448), PG64-22	CU. YD.	4.1		
12	ITEM 441 - 1-3/4" ASPHALT CONCRETE, TYPE 2 INTERMEDIATE COURSE, (448), PG64-22	CU. YD.	4.8		
13	ITEM 644 - CROSSWALK LINE, AS DIRECTED BY ENGINEER	FOOT	-		
14	ITEM 644 - STOP LINE, AS DIRECTED BY ENGINEER	FOOT	-		
15	ITEM SPECIAL - IN PLACE HOT REUSED ASPHALT PAVING, AS PER DS-6	SQ. YD.	5,205		
SUBTOTAL PAVEMENT					

CITY OF CLEVELAND, MAYOR'S OFFICE OF CAPITAL PROJECTS, DIVISION OF ENGINEERING AND CONSTRUCTION					
2026 RECYCLED ASPHALT DEMO (IFB 101-26)					
ADDENDUM #2					
TALFORD AVE. SCHEDULE OF ITEMS					
REF NO.	DESCRIPTION	UNIT	APPROXIMATE TOTAL QUANTITY	UNIT COST	ESTIMATED COST
PROJECT INCIDENTALS					
16	ITEM 614 - MAINTAINING TRAFFIC	LS	1		
17	ITEM 614 - MOBILIZATION	LS	1		
18	ITEM SPECIAL - MAKING AND CURING CONCRETE TEST CYLINDERS IN THE FIELD, AS PER D-76	SETS	1		
19	ITEM SPECIAL - FORCE ACCOUNT AS PER D-13	LS	1		
20	ITEM SPECIAL - FEES (1% of TOTAL SUM OF BID ITEMS)	LS	1		
SUBTOTAL PROJECT INCIDENTALS					
UNOFFICIAL TOTAL SUM (BID ITEMS 1-20) - (*)					
ALL QUANTITIES ARE APPROXIMATE AND NOT GUARANTEED.					
* The amount of the Bid Bond or Cashier's Check required of all bidders under Section A-7 and the amount of the surety bond required of the successful bidder under Section 19, shall be based upon this dollar figure.					
** Please see Exhibits C-1 through C-1A for proposed locations					